



STANDARD RESIDENTIAL KIT

E8-9X8

8'0" - 9'0" X 8'0" X 2"

5 S / 3 H

Extension, 14ga Hinges, WHITE NYLON Rollers

2" TRACK STANDARD LIFT JB&F ON TRACK Mount to WOOD

QTY	UOM	P/N	DESCRIPTION	NOTES
HARDWARE PARTS				
4	EA	4-9-7	3" PULLEY	
2	EA	4-9-10	3" FORK	
2	EA	3-31-1	RESIDENTIAL TOP BRACKET	
1	PR	3-37-1	BB-100	
2	EA	7-23-1	CLOSED GRIP LIFT HANDLE	
2	EA	7-25-2	VERTICAL STEP PLATE	
12	EA	4-11-16	2" SHORT STEM WHITE NYLON W/BRG ROLLER	
6	EA	3-19-1	#1 14 GA HINGE	
2	EA	3-19-2	#2 14 GA HINGE	
2	EA	3-19-3	#3 14 GA HINGE	
2	EA	3-19-4	#4 14 GA HINGE	
1	PR	4-7-26	1/8 7 X 7 X 14'0" EXT CABLE (FOR 8')	
1	PR	4-6-2	1/8 7 X 7 X 10' SAFETY CABLE	
1	EA	7-10-2	RESIDENTIAL UNILOCK	
6	FT	9-12-1	PULL ROPE	
1	EA	9-30-4	LABEL#1 - SPRING IS LOADED	
1	EA	9-30-5	LABELS #2 STD BCK & #3 UDR TSN	
FASTENERS				
68	EA	8-2-3	1/4 X 1 TEK	
8	EA	8-2-31	1/4 X 1 TEK PAINTED RED	
4	EA	8-2-7	1/4 X 5/8 RIBBED NECK TRACK BOLT	
4	EA	8-2-10	1/4 WHIZ NUT	
12	EA	8-3-17	5/16 X 1-5/8 HWH LAG DEEP HEAD	
2	EA	8-3-4	5/16 X 3 OPEN EYE BOLT	
4	EA	8-3-6	5/16 WHIZ NUT	
4	EA	8-4-1	3/8 X 1-1/2 HH MACHINE BOLT	
2	EA	8-4-2	3/8 X 3/4 RH CARRIAGE BOLT	
6	EA	8-4-4	3/8 WHIZ NUT	
1	EA	8-8-1	#6 SCREW EYE	
2	EA	4-8-1	3 HOLE CABLE CLIP	
2	EA	8-2-1	1/4 X 2-1/4 LARGE "S" HOOK	